




# McClellan Creek Water Tank Replacement

The city of East Helena completed the replacement of two leaky water storage tanks with a single one-million-gallon water tank. Project construction began in March 2022 and was completed the following September. The new water tank will supply the City of East Helena with increased water capacity that can accommodate future community growth and keep the city's drinking water safe!



**Over 77% of this project was funded using grants!**



# Prickly Pear Creek

## Watermain Crossing

A 10-inch HDPE watermain was directionally drilled under Prickly Pear Creek and connected to the City's water distribution system. This watermain eliminated a dead-end watermain which improved fire flow and eliminated stagnation.





# MT Highway 12

## Watermain Crossing

The city of East Helena is nearly complete with a bore and jack watermain crossing under MT Highway 12 and the adjacent railroad. A 36-inch steel casing pipe was completed in 2022 and a 14-inch HDPE watermain will be installed in the spring of 2023. This crossing looped in the Manlove Street main to the existing distribution system, eliminate the existing dead-end near the Chemet Complex, and increase fire flow south of Highway 12.

